

London Complete Streets Plan

December 2021



Prepared by:

**Tulare County Resource
Management Agency**



Paid for by a grant from:



London Complete Streets Plan




{This Page Intentionally Left Blank}

,



London Complete Streets Plan



Tulare County Resource Management Agency
Economic Development and Planning Branch
5961 S Mooney Boulevard
Visalia, CA 93277-9394
(559) 624-7000

London Complete Streets Plan



{This Page Intentionally Left Blank}



London Complete Streets Plan



Tulare County Board of Supervisors

Larry Micari – District 1
Pete Vander Poel – District 2
Amy Shuklian – District 3 (Chair)
Eddie Valero – District 4 (Vice Chair)
Dennis Townsend – District 5

Tulare County Planning Commission

Dennis Lehman – District 1
Vacant – District 2
Bill Whitlatch – District 3
Maria McElroy – District 4 (Chair)
Steve Pearson – District 5 (Vice Chair)
Wayne O. Millies – At Large
Ed Dias – At Large
Gil Aguilar – District 2 (Alternate)

County Administrative Office

Jason T. Britt, CAO

Tulare County Resource Management Agency

Reed Schenke, Director
Michael Washam, Associate Director
Aaron Bock, Assistant Director
Hernan Beltran Herrera, Chief Engineer
Chuck Przybylski, Planner IV
Susan Simon, Planner III
Jose Saenz, Planner III
Michael Winton, Engineer IV
Johnson Vang, Engineer III
Julian Sanchez, Engineer I
Eliza Gonzalez, Administrative Aide

London Complete Streets Plan

{This Page Intentionally Left Blank}

London Complete Streets Plan

TABLE OF CONTENTS

INTRODUCTION	1
Complete Streets Vision	1
Complete Streets Definition	1
Complete Streets Attributes	2
Report Outcomes	2
Conclusions and Future Funding Opportunities	3
COMPLETE STREET POLICIES	3
Complete Street Goals	3
Complete Streets Objectives	4
Complete Streets Policies	4
Tulare County General Plan Policies	4
Complete Street Policy Design Criteria	5
Complete Street Mobility Plan	5
Caltrans and Complete Streets	6
Bicycle Facilities	7
Pedestrian Facilities	8
Transit Facilities	9
Cost Benefits Analysis, Implementation, and Funding Mechanisms	9
Benefits of Complete Streets	10
Community Specific Complete Street Implementation Measures	11
Measure R	11
Active Transportation Program (ATP)	11
Public Outreach Efforts	12
London Public Zoom Meetings	12
DESIGN FACILITIES	13
Improvement Standards	13
IMPLEMENTATION	14
Selection of Communities	14
PROJECTS	15
Complete Streets Project Plans	15
Cost Estimates	15

London Complete Streets Plan

FIGURES

Figure 1 - Tulare County Class 1, 2 & 3 Two Lane Roads.....	13
Figure 2 - Tulare County Class 3 Four Lane Road.....	13

APPENDIX

Appendix A – Proposed Complete Streets Projects
Appendix B – Circulation Plan
Appendix C – Bicycle, Bus and Pedestrian Plan
Appendix D – Road Maintenance Plan
Appendix E – Cost Estimates for London
Appendix F – London 30% Submittal Plan Set
Appendix G – Complete Streets Outreach

London Complete Streets Plan

{This Page Intentionally Left Blank}

London Complete Streets Plan

Introduction

Complete Streets Vision

The California Complete Streets Act (AB 1358) of 2008 was signed into law on September 30, 2008. Beginning January 1, 2011, AB 1358 requires circulation elements to address the transportation system from a multimodal perspective. The bill states that streets, roads, and highways must “meet the needs of all users in a manner suitable to the rural, suburban, or urban context of the general plan.”

The Tulare County Resource Management Agency (RMA) is committed to fully integrating modal options in its General Plan and various Community Plans within Tulare County. This includes supporting projects that enhance walking and bicycling infrastructure. Additionally, RMA will improve access to public transportation facilities and services. This includes supporting urban development patterns and Americans with Disabilities Act (ADA) infrastructure that allow for greater accessibility to transit stops and stations. Finally, RMA continues to improve safety for all users and encourages street connectivity to create a comprehensive, integrated and connected circulation network. This is particularly important for those who rely on transportation infrastructure to be physically active and for students who walk or bike to school.

Steady population growth in Tulare County has directly impacted transportation needs. In the past, many of Tulare County’s federal, state, and local funding sources were used to develop new or improved traffic signals, interchanges, provide more travel lanes and to maintain existing roadway facilities. Historically, these funding sources have run well short of what is needed. The typical roadway transportation project that adds capacity and infrastructure is insufficient given these conditions. The RMA must adhere to its vision, which is to “provide a safe, convenient and effective County transportation system that enhances mobility and air quality for residents and visitors.”

Recent RMA and RMA-supported projects have already fulfilled some of these desires. There are already expanded bus transit routes in the County and more are being constructed for implementation in the near future. New transit centers are being placed throughout the County and efforts are underway to add more bicycle lanes and routes. Recent planning studies are looking to improve roadway safety, pedestrian safety, and access management between roadways and building developments. These efforts are consistent with green house gas (GHG) emissions reductions efforts to reduce vehicle miles travelled (VMT) set forth under SB 375.

Promoting Complete Streets projects can offer Tulare County the ability to reduce traffic congestion, improve air quality, and increase the quality of life of residents by providing safe, convenient, and comfortable routes for walking, bicycling, and public transportation. Integration of Complete Streets into Tulare County’s existing policies allows the potential to prevent chronic diseases, reduce motor vehicle related injury and deaths, improve environmental health, stimulate economic development, and ensure access of transportation options for all people in Tulare County.

Complete Streets Definition

Complete Streets are roadways designed to safely and comfortably accommodate all users, regardless of age, ability or mode of transportation. Users include motorists, cyclists, pedestrians and all vehicle types, including public transportation, emergency responders, and freight and delivery trucks among others. In addition to providing safety and access for all users, Complete Street design treatments take into account

London Complete Streets Plan

accommodations for disabled persons as required by the ADA. Design considerations for connectivity and access management are also taken into account for non-motorized users of the facility.

Implementation of Complete Street design treatments will be based on whether it connects the networks for all modes, whether it improves the functionality for all users, and whether it is appropriate given the surrounding context of the community. The final elements of a Complete Street roadway will be largely based on these factors. At a minimum, a Complete Street roadway includes sidewalks and sidewalk amenities, transit shelters and facilities whenever there is a route along the corridor, and provisions for bicycle facilities.

Complete Streets Attributes

While every street cannot be designed to serve all users equally, there are opportunities to enhance service for all users while maintaining its principal transportation function. Complete Streets incorporate community values and support adjacent land uses while ensuring safety and mobility. Proper applications of Complete Streets concepts support sustainable growth and preservation of scenic, aesthetic and historic resources.

Report Outcomes

As a part of the Circulation Element for the Community Plan Update, this Complete Streets Report (Implementation Work Plan) and the following Implementation and Policies Section achieved the following outcomes:

- (i) *Addressed* congestion, climate change and oil dependence by shifting to lower-carbon modes;
- (ii) *Improved* safety by addressing shoulders, sidewalks, better bus placement, traffic speed reduction, treatments for travelers with disabilities;
- (iii) *Created* “livable communities” by encouraging walking and bicycling for health, and by providing a safe walking and bicycling environment as an essential part of improving transportation movement and safety within the roadways studied.

These outcomes are achieved by the following:

- (a) *Included all users* namely, pedestrians, bicyclists, transit vehicles and users, and motorists. In drafting this report, all users were invited to comment on how the County could better serve the community. The implementation of complete streets directly shifts the emphasis to lower-carbon (using) modes of transportation. The shift from the gas using automobile to pedestrian and bicycle transport is achieved through the creation of sidewalks, improving sidewalks, and including bike lanes and/or bike routes for a wider ranger of people to use. The shift to transit is included in improving policies, programs and facilities in the operations of County’s transit systems.
- (b) *Created a comprehensive integrated and connected network* that supports “livable communities” that promote a safe interwoven fabric are provide for by the Policies Section using the transportation goals in the 2030 General Plan Circulation Element and by further defining complete streets network (see Appendix C).

London Complete Streets Plan

- (c) *Emphasized flexibility* recognizing that all streets with these communities are different, and thus, balancing user needs. No one standard was applied to all streets and the street designs were adjusted to existing conditions, differing jurisdictions and the desires of the community.
- (d) *Considered both new and retrofit projects*, including design, planning, maintenance, and operation, for the entire right-of-way within these communities. In addition to the various sections discussed below Appendix A – D include plans that show the plans, designs, and existing and proposed maintenance plans and operations of the Complete Streets Plan.
- (e) *Used the latest and best design standards*. By using newer design standards as represented in the preliminary design plans versus the County’s Roadway Standards the County is able to provide wider sidewalks and include such amenities as traffic calming measures (bulbouts).
- (f) *Conducted extensive public outreach* to ascertain the solutions that best fit within the context of these communities. The community was consulted every two weeks throughout the 3 month window that this report was drafted. Two “walkability” audits were conducted in July. This culminated in two meetings, wherein the Community provided final feedback on the preliminary designs.

Conclusions and Future Funding Opportunities

The intended effect of identifying the outcomes and reaching the conclusions in this report is that future funding opportunities will be enhanced because the Community will be supported by fully updated Community Plans. The conclusion to the report includes the Circulation Element of the Community Plan including the policies, and plans. The other conclusion to the report includes preliminary design drawings.

Specifically, the funding sources that are found in the Funding Section will be pursued actively by Tulare County to complete the work identified in the studies include, but are not limited to, the following:

- SB 1 - Sustainable Communities Planning Grant – Complete Streets

Complete Street Policies

Complete Street Goals

The purpose of the RMA Complete Streets Policy is to create a comprehensive and uniform Complete Streets vision and policy for Tulare County. This will allow the implementing entities to incorporate Complete Streets guidelines and standards into both development and redevelopment actions. The County’s goals are:

- Tulare County’s transportation network will be supported through a variety of feasible transportation choices, which allows for sustainable growth.
- The livability of neighborhoods and commercial centers located along the County’s transportation corridors will be enhanced by a safe and inviting pedestrian environment.

London Complete Streets Plan



- The design of multimodal roadway facilities will not compromise the needs of larger vehicles such as transit vehicles, fire trucks and freight delivery trucks.
- Inclusion of Complete Streets design elements will allow for design flexibility on different street functions and neighborhood contexts.
- Inclusion of Complete Streets design elements will improve the integration of land use and transportation, while encouraging economic revitalization through infrastructure improvements.

Complete Streets Objectives

- To create an integrated and connected transportation network that supports transportation choices and sustainable growth.
- To ensure that all transportation modes are accommodated to the extent possible in all public roadway facilities in the County.
- To develop and use the latest design standards and guidelines in the design of Complete Streets.
- To provide flexibility in the implementation of this policy so that streets chosen for implementation of Complete Streets elements can be developed to fit within the context of their principal purpose and surroundings without compromising the safety of users and needs of larger vehicles.

Complete Streets Policies

Tulare County General Plan Policies

The Tulare County General Plan Update (2030) in complying with AB 1358 calls for Four (4) Complete Streets related principles including:

Principle 1: County-wide Collaboration

Support countywide transportation plans that provide choices in travel modes.

Principle 2: Connectivity

Emphasize connectivity among cities, communities, and hamlets to ensure County residents have access to jobs and services.

Principle 3: Community Circulation

Anticipate and provide transit, traffic, and roadway connections that support the interconnectivity of all communities.

Principle 4: Pedestrian and Bicycle Facilities

Plan for the development and expansion of pedestrian paths and bicycle facilities that provide residents, with alternative modes of travel.

London Complete Streets Plan

These principles are expressed mainly in following policies including:

- TC-1.6 Intermodal Connectivity
- TC-1.7 Intermodal Freight Villages
- TC-5.1 Bicycle/Pedestrian Trail System
- TC-5.2 Non-motorized Modes in Planning and Development

Complete Street Policy Design Criteria

1. Tulare County promotes the incorporation of Complete Streets concepts and design standards in all appropriate new and retrofit County public streets (except State highways and freeways).
2. Tulare County will seek every opportunity to provide funding for the planning, design, and implementation of Complete Streets.
3. New Class I Multi-use Paths should be a minimum of eight (8) feet wide.
4. New Class II Bike Lanes should be a minimum of five (5) feet wide.
5. New sidewalks should be a minimum of five (5) feet wide.
6. Bulb-outs should be considered in areas of higher speed (35 mph or greater) where sufficient turning radii for trucks is available or as determined by the County Engineer.
7. As determined by the County Engineer, installation of posted speed limit vehicle activated traffic calming signs (VATCS) are encouraged in instances of high speed to promote safety.
8. Transit shelters and benches are encouraged at all County transit stops if FTA grants are available.
9. Street lighting and cross walk are encouraged to promote safety if considered feasible by the County Engineer.
10. Design policies should be consistent with the Tulare County Improvement Standards; other references include existing design guides, such as those issued by Caltrans, AASHTO and the ADA Accessibility Guidelines.
11. Public streets excluded from this policy include those where:
 - Complete streets concepts are in conflict with existing laws, codes, or ordinances.
 - Compliance with this policy would conflict with goals or physical conditions related to the unique aspects of the location.
12. Exceptions from Complete Street Policies:
 - Accommodation is not necessary where non-motorized use is prohibited, such as freeways.
 - Cost of accommodation is excessively disproportionate to the need or probable use as determined by the County Engineer.
 - A documented absence of current or future need.

Complete Street Mobility Plan

The California Complete Streets Act (AB 1358) of 2008 was signed into law on September 30, 2008. Beginning January 1, 2011, AB 1358 requires circulation elements to address the transportation system

London Complete Streets Plan

from a multimodal perspective. The bill states that streets, roads, and highways must “meet the needs of all users in a manner suitable to the rural, suburban, or urban context of the general plan.” Essentially, this bill requires a circulation element to plan for multimodal transportation accommodating all modes of transportation where appropriate, including walking, biking, car travel, and transit. The current functional classification system plan is shown in Appendix B.

The Complete Streets Act also requires circulation elements to consider the multiple users of the transportation system, including children, adults, seniors, and the disabled. For further clarity, AB 1358 tasks the Governor’s Office of Planning and Research to release guidelines for compliance with this legislation by January 1, 2014. Implementation of complete streets principles should be tailored to the individual jurisdiction and the individual roadway. The Complete Streets Program for Tulare County focuses on a network-based approach that has been tailored to the needs of the Community of London. Another principle that is being applied is under SB 743, requiring a change to evaluating traffic using Vehicle Miles Traveled verses Level of Service under CEQA analysis, and under AB 32 in reducing Green House Gasses.

Complete Streets: According to the National Complete Streets Coalition, complete streets are a means by which, “... planners and engineers (can) build road networks that are safer, more livable, and welcoming to everyone.... Instituting a complete streets policy ensures that transportation planners and engineers consistently design and operate the entire roadway with all users in mind – including bicyclists, public transportation vehicles and riders, and pedestrians of all ages and abilities.”

Network-Based Complete Streets: Combines individual travel mode networks into one multimodal transportation system, integrating infrastructure where appropriate, ultimately ensuring that all users can safely and efficiently access their destination.

Vehicle Miles Traveled (VMT): Vehicle miles traveled is the metric that identifies the total distance traveled in a car per driver. VMT drives roadway needs (the more people who drive, the more capacity and maintenance are needed on the roadway system). Under the Tulare County Climate Action Plan, in reducing VMT green house gas emissions are reduced and the County has an overall target of reducing 6% of its green house gas emissions through a reduction in VMT.

Community Plans adopt these principles, which are combined into the following mission statement:

The Community Complete Streets Network comprises four types of facilities—vehicular, pedestrian, bicycle, and public transit. This complete streets approach will enable residents to choose which travel mode best suits them. It also will ensure that streets are designed with the users in mind—accommodating for businesses, children, the elderly, bicyclists, and transit users.

Caltrans and Complete Streets

Under Caltrans District Order 64-R1, Caltrans requires that a Complete Streets Implementation Action Plan be developed and implemented for Caltrans owned and maintained Streets. Their Implementation Action plan provides a background by which the Tulare County Completes Street Plan will be implemented.

London Complete Streets Plan

TCAG, Tulare County Regional Bicycle Transportation Plan, Regional Transportation Plan (RTP) and Sustainable Communities Strategy (SCS)

TCAG in 2014 updated a Regional Bicycle Plan that does not include any bicycle facilities through the Community of London. TCAG funded the grant for this Complete Streets Policy and in the RTP Action Element describe bicycle circulation patterns and Pedestrian policies focusing on the Americans with Disabilities Planning Strategies and Transportation Demand Management to increase pedestrian activity. In addition, rail and goods movement is part of the Sustainable Communities Strategy in lieu of utilizing diesel powered freight trucks.

Tulare County Climate Action Plan (CAP)


The Tulare County CAP calls for a reduction on a project (over 50 vehicles) by project basis of 6% through a mixture of measures that are spelled out in Appendix J of the CAP. Utilization of alternative means of transportation will reduce GHG emissions and will help projects and the region meet their targets.

Bicycle Facilities

Bicycle facilities consist of Class I, Class II, and Class III facilities as defined below. In Tulare County, this General Plan and the Bicycle Transportation Plan envision a system of bicycle lanes on roadways that will connect the activity centers of the communities to the residents. County has identified pedestrian corridors on the Community of London Bicycle, Bus and Pedestrian Plan (see Appendix C).

Class I


Bike path providing completely separated right-of-way designated for the exclusive use of bicycles and pedestrians. In Tulare County, Class I facilities will primarily be implemented through TCAG. Future bicycle facilities have also been identified through the *Bicycle Transportation Plan* (TCAG - 2010). There is no existing or proposed Class I bicycle facilities in London.



London Complete Streets Plan


Class II

Bikeway that provides designated lanes for the use of bicycles through the use of striping on the roadway and signage designations for the facility.



Class III

Bikeway that provides route designation by signage. Roadways are shared between bicyclists and motorists. Class III facilities in Tulare County are envisioned to be implemented along the major circulation segments of roadway that connect the overall County roadway network.



Pedestrian Facilities

Pedestrian Paths and Sidewalks

Pedestrian paths are primarily developed as part of the roadway and trail systems of a community and reflect the interconnected nature of circulation and transportation systems as a whole. Constructing wide streets increases the distance a pedestrian must travel to cross a street, thereby making it inconvenient for

London Complete Streets Plan

public use and inhibiting pedestrian circulation in the community. Currently, limited continuous sidewalks are provided along major routes in the community. In addition to connecting available pedestrian resources, the communities have prioritized the completion of sidewalks along safe routes to school. Enhanced pedestrian crossings and sidewalks is considered in areas where high pedestrian demand occurs (such as to and around schools).

Multiuse Trails

Multiuse trails are facilities that can be used by bicycles, pedestrians, equestrians, and other recreational users. No multiuse trails exist or are proposed in London.

Transit Facilities

Transit options give users the ability to get to a destination without relying on the automobile. This also provides other community benefits, including reduced vehicle miles traveled (VMT). Reducing VMT will help the County achieve their greenhouse gas reduction target,

Public transportation services and facilities in Tulare County consist of public bus service, paratransit service, and could also consider park-and-ride locations.

Public Bus Service

Public bus service is provided by Tulare County Area Transit (TCaT) in rural areas such as London and by local City transit agencies in transitioning areas, which enables commuters to travel within the communities and adjacent cities with minimal transfers. Existing transit routes and designated bus stops are shown in the following figures.

Tulare County Area Transit (TCAT)

Transit service is provided in London through the Tulare County Area Transit (TCAT). Additionally, Tulare County has provided guidance for including transit within facilities. These guidelines should be applied when considering new development to ensure appropriate connectivity and design features to support bus service.

Paratransit Service

Paratransit is an alternative mode of passenger transportation that does not follow fixed routes or schedules. Typically, vans or minibuses are used to provide paratransit service. Paratransit services vary considerably on the degree of flexibility they provide their customers. The most flexible systems offer on-demand, call-up, door to door service from any origin to any destination in a service area.

Park-and-Ride Lots

Park-and-ride lots provide places for people to meet up and carpool to areas outside of the Community. A Park and Ride facility could also provide a compressed natural gas refueling station. As the community's population grows and given the large number of commuters, a park-and-ride location would be best sited near the edges of the Community along Avenue 192.

Cost Benefits Analysis, Implementation, and Funding Mechanisms

Caltrans lists the following benefits of Complete Streets in their implementation plan. They include:

London Complete Streets Plan

- Increased Transportation Choices: Streets that provide travel choices can give people the option to avoid traffic congestion, and increase the overall capacity of the transportation network.
- Economic Revitalization: Complete streets can reduce transportation costs and travel time while increasing property values and job growth in communities.
- Improved Return on Infrastructure Investments: Integrating sidewalks, bike lanes, transit amenities, and safe crossings into the initial design of a project spares the expense of retrofits later.
- Quality of Place: Increased bicycling and walking are indicative of vibrant and livable communities.
- Improved Safety: Design and accommodation for bicyclists and pedestrians reduces the incidence of crashes.
- More Walking and Bicycling: Public health experts are encouraging walking and bicycling as a response to the obesity epidemic. Streets that provide room for bicycling and walking help children get physical activity and gain independence.

Benefits of Complete Streets

The health benefits from walking and bicycle riding include increased overall health, and a reduction in air quality and green house emissions. According to the Caltrans accepted, Victoria Transport Policy Institute, walking has a \$.25 per mile health benefit, while the cost of Greenhouse Gas (GHG) reductions is \$23 per ton. According to the Federal Highway Administration, sidewalks reduce incidences to pedestrians over 80%. According to Caltrans, the average costs of highway incidents are stated below.

Var.	Definition	Value	Unit	Source
V	Daily volume, by vehicle type (passenger vehicle, truck), period (peak, non-peak), facility (HOV, non-HOV, weaving)	#	Trips/Day	User Input
Dist	Project length (distance traveled)	#	Miles per trip	User Input
CostFatal ^{Tr}	Cost per Fatality (Transit)	\$9,800,000	\$/event	1
CostInj ^{A,Tr}	Cost per Level A Injury (Severe) (Transit)	\$466,400	\$/event	1
CostInj ^{B,Tr}	Cost per Level B Injury (Moderate) (Transit)	\$127,000	\$/event	1
CostInj ^{C,Tr}	Cost per Level C Injury (Minor) (Transit)	\$64,900	\$/event	1
CostPD ^{Transit}	Cost per Property damage (Transit)	\$2,700	\$/event	2
CostFatal ^{t,d}	Cost per Accident Fatality (Highway)	\$10,800,000	\$/accident	1
CostInj ^{t,d}	Cost per Accident Injury (Highway)	\$148,800	\$/accident	1
CostPD ^{t,d}	Cost per Accident PDO (Highway)	\$9,700	\$/accident	1
CostAVG	Average Cost per Accident (Highway)	\$185,600	\$/accident	1
FatalAcc ^{t,d}	Fatal Accident Rate	0.006	per mil veh-mi	3
InjAcc ^{t,d}	Injury Accident Rate	0.29	per mil veh-mi	3
PDAcc ^{t,d}	PDO Accident Rate	0.55	per mil veh-mi	3
NFAcc ^{t,d}	Non-Freeway Rate	1.05	per mil veh-mi	4

London Complete Streets Plan



Community Specific Complete Street Implementation Measures

As part of a network-based approach, the County has identified (and will implement through pursuing further roadway studies and infrastructure design updates) a complete network for pedestrians. The County will also work to deliver infrastructure to support all modes of transportation. In addition to the General Plan Circulation Element Implementation Section, the key implementation measures include:

1. Evaluating Roadways as potential Bike/Pedestrian travel routes,
2. Completing pedestrian infrastructure, as appropriate,
3. Providing safe and accessible pedestrian facilities in high use areas,
4. Designing and building sidewalks for safer routes to school,
5. Designating roadways for bicycle routes that are aligned with the Tulare County comprehensive bicycle network,
6. Coordination with County Transit.
7. Submitting the following list of project and cost to TCAG and Caltrans for consideration under further grant funding opportunities.

Measure R

Bike/Transit/Environmental Projects (14% of Measure R Funding)

On November 7, 2006, the voters of Tulare County approved Measure R, imposing a ½ cent sales tax for transportation within the incorporated and unincorporated area of Tulare County for the next 30 years. The transportation measure will generate slightly more than \$652 million over 30 years to Tulare County's transportation needs.

The Goals of Measure R include air quality improvement efforts that will be addressed in the Measure R Expenditure Plan through the Transit/Bike/Environmental Program, which includes funding for transit, bike, and pedestrian environmental projects. The goal of this program is to expand or enhance public transit programs that address the transit dependent population, improve mobility through the construction of bike lanes, and have a demonstrated ability to get people out of their cars and improve air quality and the environment.

Active Transportation Program (ATP)

On September 26, 2013, Governor Brown signed legislation creating the Active Transportation Program (ATP) in the Department of Transportation (Senate Bill 99, Chapter 359 and Assembly Bill 101, Chapter 354). The ATP consolidates existing federal and state transportation programs, including the Transportation Alternatives Program (TAP), Bicycle Transportation Account (BTA), and State Safe Routes to School (SR2S), into a single program with a focus to make California a national leader in active transportation.

London Complete Streets Plan

Citizen Feedback

Public Outreach Efforts

The purpose public workshops or community meetings is to engage in discussions with local residents and business owners regarding specific topics, e.g., transportation related improvements. Public outreach efforts were held in several formats including formally and informally. Formal community meetings were held at local schools, community service districts/public utility districts (CSDs/PUDs), town council forums and other well-known locations. Informal meetings were conducted with individual business or property owners associated to specific access concerns or other issues.

Publicity for meeting times and locations generally consisted of newspaper releases, local newsletter informational items, citizens distributing fliers, handing out bi-lingual fliers to school children to be given to the student's guardian, posting fliers at local community businesses, local school board meeting agendas, area congressional office and non-profit agency assistance, local senior centers and health clinics (if applicable), email and other forms of communication. Formal public meetings were held in the various communities shown below. A summary of additional information – Tulare County Resource Management Agency Complete Streets and Community Plan Outreach (2021) – is located in Appendix G.

London Public Zoom Meetings

- June 3, 2021
- June 17, 2021
- July 8, 2021

Complete Streets Workshop held at the Hodes Community Center in London

- July 22, 2021

Community feedback was gathered at the June d July meetings and incorporated into the design of the Complete Street Plans and further discussed at the in person July meeting to receive further community feedback. These designs were edited to include feasible improvements and cost estimates were assigned to each project within the respective community for each study roadway segment.

London Complete Streets Plan

Design Facilities

Improvement Standards

The purpose public workshops or community meetings is to engage in discussions with local residents and business owners regarding specific topics, e.g., transportation related improvements. Transportation related facilities for public use are built within existing right of way (R/W) owned by a public agency, e.g., county, city or state. Within this R/W is a standard cross section, which is a term that is used to define the configuration of existing or proposed roadways at right angles to the centerline (CL). Typical sections show the width, thickness and descriptions of the pavement section, as well as the geometrics of the graded roadbed, side improvements and side slopes.

In Tulare County, the two most common cross sections are shown for two or four lane roads, varying in width based upon the number of lanes, parking, sidewalks, shoulders, bike lanes, etc. Figure 1 shows the cross section for two lane roads and Figure 2 identifies a typical four lane cross section.

Figure 1 - Tulare County Class 1, 2 & 3 Two Lane Roads





Figure 2 - Tulare County Class 3 Four-Lane Road



London Complete Streets Plan

Tulare County Pavement Management System

Pavement Management

Pavement management is the process of planning the maintenance and repair of a network of roadways or other paved facilities in order to optimize pavement conditions over the entire network. Pavement management incorporates life cycle costs into a more systematic approach to minor and major road maintenance and reconstruction projects. The needs of the entire network as well as budget projections are considered before projects are executed. Pavement management encompasses the many aspects and tasks needed to maintain a quality pavement inventory, and ensure that the overall condition of the road network can be sustained at desired levels.

Pavement Management System

The Tulare County Pavement Management System (PMS) is a planning tool used to aid pavement management decisions. PMS software programs model future pavement deterioration due to traffic and weather, and recommend maintenance and repairs to the road's pavement based on the type and age of the pavement and various measures of existing pavement quality. Measurements can be made by persons on the ground, visually from a moving vehicle, or using automated sensors mounted to a vehicle. PMS software assists RMA staff to create composite pavement quality rankings based on pavement quality measures on roads or road sections. Recommendations are usually biased towards preventive maintenance, rather than allowing a road to deteriorate until it needs more extensive reconstruction.

Typical tasks performed by Tulare County PMS include:

- Inventory pavement conditions, identifying good, fair and poor pavements;
- Assign importance ratings for road segments, based on traffic volumes, road functional class, and community demand;
- Schedule maintenance of good roads to keep them in good condition; and,
- Schedule repairs of poor and fair pavements as remaining available funding allows.

Research has shown that it is far less expensive to keep a road in good condition than it is to repair it once it has deteriorated. This is why pavement management systems place the priority on preventive maintenance of roads in good condition, rather than reconstructing roads in poor condition. In terms of lifetime cost and long-term pavement conditions, this will result in better system performance.

The County is proposing a Road Maintenance Plan (see Appendix D) for the community of London that is a result of the PMS.

Implementation

Selection of Communities

An effort is under way in Tulare County to implement Complete Streets Policies in the unincorporated communities within Tulare County's boundary. Just as the County updated its General Plan in 2012, many of the Community Plans are going through the update process. As a result of the Community Plan

London Complete Streets Plan

update process, several public meeting have been held in order to garner input from the local residents and business owners. Balancing the needs of what the people want while following local, state and federal policies and laws with a limited amount of available funding is the principal challenge in each community.

Transportation and related infrastructure costs tend to be exceedingly high may take years to implement. For purposes of this Study, four transportation corridors were selected within the community (see Appendix A), and two roadway segments in the community were selected to be evaluated for implementation of Complete Street standards. These roadway segments generally represent the highest volume roadways with a blend of residential and mixed land uses that also provide for regional access. Local streets and freeways were not selected, however tying into these facilities is considered.

General themes that were voiced from residents in each community related to transportation included the need for:

- Sidewalks
- Better road conditions
- Safe walking and biking areas
- Street lights
- Pedestrian crossings
- Safe (lower) vehicle speeds
- Improved drainage
- Increased transit stops
- Improved connectivity (railroad crossings)

Given the information provided by the residents and business owners, conceptual layouts and designs based upon the citizens concerns were presented to collect input. Based upon the community planning process, the following sections identify proposed projects for each community.

Projects

Complete Streets Project Plans

The plans and projects in the appendices are identified as part of the complete streets policy to identify corridors for various user types and to demonstrate examples of design policies. These plans and are the result of input obtained through the community outreach process, multiple Tulare County agencies and divisions and professional engineering consultants.

Complete Streets Funding Opportunities

The following sections identify opinions of probable cost estimates for Complete Street transportation related improvements in London. As shown in the tables, the funding sources include local, state and federal programs. Typically, local matches are required for acquiring state and federal funds. Measure R, a Tulare County sales tax for transportation, is available for such matches.

Cost Estimates

Detailed cost estimates are included in the Appendix F

London Complete Streets Plan



Appendix A – Proposed Complete Streets Projects

London Complete Streets Plan

{This Page Intentionally Left Blank}

London Complete Streets Plan

Appendix B – Circulation Plan

London Complete Streets Plan

{This Page Intentionally Left Blank}

Legend

- Local
- Collector (Major)
- Arterial (Minor)
- Collector (Minor)
- Urban Development Boundary



Community of London Circulation Plan

ROAD 56

AVENUE 384

London

DENVER

AVENUE 378

ROAD 58

KATE

ROAD 57

AVENUE 377

HUNTER

AVENUE 376

ROAD 60

0 500 1,000 2,000 Feet

London Complete Streets Plan



Appendix C – Bicycle, Bus, and Pedestrian Plan

London Complete Streets Plan



{This Page Intentionally Left Blank}

Legend

-  Pedestrian Route
-  Bus Route
-  Bus Stops
-  Urban Development Boundary



Community of London
Bicycle, Bus, & Pedestrian Plan



London Complete Streets Plan



Appendix D – Road Maintenance Plan

London Complete Streets Plan



{This Page Intentionally Left Blank}

Legend

 Urban Development Boundary

 SINGLE CHIP SEAL



ROAD 64

Community of London
Road Maintenance '16-'21

AVENUE 384

London

DENVER

AVENUE 378

ROAD 58

KATE

ROAD 60

ROAD 57

AVENUE 377

HUNTER

AVENUE 376

0 500 1,000 2,000
Feet

London Complete Streets Plan



Appendix E – Cost Estimates for London

London Complete Streets Plan

{This Page Intentionally Left Blank}

London Complete Streets Plan

Cost Estimate for London

Detailed Engineer's Estimate						
Agency:		Tulare County Resource Management Agency				
Project Name:		Complete Streets- London				
Project Location:		Avenue 378 - 650' West of Rd 57 to Rd 60, Road 57-Ave 376 to Ave 378, & Kate Rd - Ave 378 to Ave 378				
Date of Estimate:		October 14, 2021				
Prepared by:		Julian Sanchez				
Construction Items						
Item No.	Caltrans Item code	Description	Units	Quantity	Unit Cost	Total
1	999990	Mobilization	LS	1	\$418,000	\$418,000
2	050126	Construction Staking	LS	1	\$50,000	\$50,000
3	120090	Construction Area Signs	LS	1	\$10,000	\$10,000
4	120100	Traffic control system	LS	1	\$20,000	\$20,000
5	130200	Prepare Water Pollution Control Program	LS	1	\$10,000	\$10,000
6	70030	Lead Compliance Plan	LS	1	\$5,000	\$5,000
7	170103	Clearing and Grubbing	LS	1	\$30,000	\$30,000
8	220101	Finishing Roadway	LS	1	\$40,000	\$40,000
9(F)	190101	Roadway excavation	CY	12468	\$90	\$1,122,178
10(F)	250201	Class 2 Aggregate Base	CY	7037	\$90	\$633,333
11	390133	Hot Mix Asphalt (Type A)	TON	7990	\$110	\$878,944
12	731504	Minor Concrete (Curb & Gutter)	LF	10100	\$30	\$303,000
13	731521	Minor Concrete (Sidewalk)	SQFT	63000	\$7	\$441,000
14	731623	Minor Concrete (Ramp)	EA	27	\$5,000	\$135,000
15	731516	Minor Concrete (Driveway/V-gutter)	SF	14215	\$15	\$213,225
16	510502	Minor Concrete (Minor Structures)	LS	1	\$20,000	\$20,000
17	391006	Paving Asphalt (Binder to Geosynthetic)	TON	3	\$5	\$17
18	393004	Geosynthetic Pavement Interlayer (Fabric)	SQYD	3333	\$5	\$16,667
19	398200	Cold Plane Asphalt Concrete Pavement	SQYD	2711	\$10	\$27,111
20		Signing & Striping	LS	1	\$15,000	\$15,000
21		Drainage Improvements	LS	1	\$150,000	\$150,000
22		Transit stops	EA	2	\$6,000	\$12,000
23		Misc Items	LS	1	\$50,000	\$50,000
					Sub-Total:	\$4,600,475
					*Contingency	\$460,048
					TOTAL:	\$5,060,523
* Up to 10% Contingency may be included in Engineer's Estimate						
(F) = Final Pay Item						
Non-Construction Related Cost						
Item No.	Caltrans Item code	Description	Units	Quantity	Unit Cost	Total
22	-	Environmental Clearance	% of CON	5%	\$4,600,475.24	\$230,023.76
23	-	Preliminary Engineering (PE)	% of CON	10%	\$4,600,475.24	\$460,047.52
24	-	Construction Engineering (CE)	% of CON	15%	\$4,600,475.24	\$690,071.29
25	-	R/W Acquisition /Admin	LS	1	\$300,000.00	\$300,000.00
26	-	Utility Relocations	LS	1	\$200,000.00	\$200,000.00
					Total:	\$1,880,142.57
Total Construction & Non-Construction Items						\$6,940,665.34


London Complete Streets Plan

Appendix F – London 30% Submittal Plan Set


London Complete Streets Plan

{This Page Intentionally Left Blank}


London Complete Streets Plan




London Complete Streets Plan




London Complete Streets Plan




London Complete Streets Plan





London Complete Streets Plan



London Complete Streets Plan



{This Page Intentionally Left Blank}



London Complete Streets Plan



Appendix G – Complete Streets Outreach

London Complete Streets Plan

{This Page Intentionally Left Blank}



Complete Streets Staff Meeting Agenda

April 13, 2021


Where We Are:

- Lindsay flyers/surveys mailed 4/7/2021
- Goshen flyers meeting mailed 4/8/2021
- Received address labels for London and West Goshen from Mr. Vang
- Matheny Tract first public outreach Tuesday, April 13, 2021 at 6:00 pm
- East Porterville first public outreach Thursday, April 15, 2021 at 6:00 pm
- Contacted Blanca Escobedo, Leadership, she will encourage residents to join.
- Plainview topo's have been received
- East Tulare Villa topo's ordered
- Comment Spreadsheets for the following communities:
 - Goshen
 - East Tulare Villa
 - Matheny Tract

Reports:

- Susan Simon
- Johnson Vang
- Michael Winton

QUEREMOS SABER LO QUE PIENSA



London Completa Calles

EN EL MAPA DIBUJE UN CÍRCULO EN LA “AREA” DE PREOCUPACIÓN EN LAS CARRETERAS EN LONDON EN LAS PREOCUPACIONES DE LA LISTA DE ABAJO

- Seguridad, congestión, velocidad de vehículos, farola, paso de peatones.
- Baches, inundaciones, instalaciones de drenaje, pavimentar la carretera.
- Bordillo, alcantarilla, acera, rampas de bordillo.
- Paradas de tránsito y de autobús escolar, carriles de bicicletas.

¡También apreciamos cualquier comentario que pueda hacer!



VISIÓN COMMUNITARIA

PLANIFICACIÓN COMPLETA DE LA CALLE

REUNIÓN PÚBLICA

APORTE DE COMUNIDAD

Volver a la dirección


Tulare County
Resource Management Agency
5961 S. Mooney Blvd.
Visalia, CA 93277

Para preguntas contactar

Susan Simon 559-624-7126
Jose Saenz (Español) 559-624-7102



WE WANT TO KNOW WHAT YOU THINK




London Complete Streets Project

CIRCLE YOUR “AREA” OF ROAD CONCERNS FOR LONDON ON THE BELOW MAP AND YOUR CONCERNS ON THE BELOW LIST

- Safety, congestion, vehicle speed, streetlights, pedestrian crossing.
- Potholes, flooding, drainage facilities, pave out of the roadway.
- Curb, gutter, sidewalk, curb ramps.
- Transit and school bus stops, bike lanes.

We also appreciate any notes you can make!



COMMUNITY VISIONING

COMPLETE STREETS PLANNING

PUBLIC MEETING

COMMUNITY INPUT NEEDED

Return to address below


Tulare County
Resource Management Agency
5961 S. Mooney Blvd.
Visalia, CA 93277

Questions Contact

Susan Simon 559-624-7126
Jose Saenz (Spanish) 559-624-7102



LONDON COMPLETE STREETS



PUBLIC OUTREACH SCHEDULE INFORMATION

Be informed. Be involved. Be heard

Virtually participate in a public meeting designed to
garner input on vision, goals, and priorities

MARK YOUR CALENDAR

PUBLIC MEETING SCHEDULE

Kick-off Session: Thursday, June 3rd at 6:00 p.m.

Study Session 1: Thursday, June 17th at 6:00 p.m.

Study Session 2: Thursday, July 8th at 6:00 p.m.

In order to provide Tulare County Resource Management Agency to set their vision and goals, the outreach sessions will be designed as mini goal setting/strategic planning/vision sessions.

LINK FOR PARTICIPATION, KICK-OFF & STUDY SESSIONS

<https://tularecounty-ca.zoom.us/j/94122633018?pwd=UUpZZ0pMUnRMZHloODIDTjN3U1ZSdz09>

Tulare County
Resource Management Agency
5961 S. Mooney Blvd.
Visalia, CA 93277

Meeting ID: 941 2263 3018

Passcode: 907610

Phone: 1 669 900 9128

Questions Contact


Susan Simon 559-624-7126
Jose Saenz (Spanish) 559-624-7102



WHAT ARE YOUR ROAD CONCERN?

- Safety, congestion, vehicle speed, streetlights, pedestrian crossing.
- Potholes, flooding, drainage facilities, pave out of the roadway.
- Curb, gutter, sidewalk, curb ramps.
- Transit and school bus stops, bike lanes.

LONDON COMPLETA CALLES



INFORMACIÓN DEL PROGRAMA DE DIVULGACIÓN PÚBLICA

Estar informado. Estar involucrado. Ser Escuchado.

Participe virtualmente en reuniones públicas diseñadas para obtener información sobre los objetivos y prioridades de la visión.

HORARIO DE REUNIONES PÚBLICAS

Iniciación:: Jueves, Junio 3 at 6:00 p.m.

Sesión de Estudio 1: Jueves, Junio 17 at 6:00 p.m.

Sesión de Estudio 2: Jueves, Julio 8 at 6:00 p.m.

Con el fin de proporcionar a la Agencia de Gestión de Recursos del Condado de Tulare para establecer su visión y metas, las sesiones de divulgación se diseñarán como mini establecimiento de metas/planificación estratégica/sesiones de visión.

ENLACE PARA LA PARTICIPACIÓN, INICIO Y SESIONES DE ESTUDIO

<https://tularecounty-ca.zoom.us/j/94122633018?pwd=UUpZZ0pMUUnRMZHloODlDTjN3U1ZSdz09>

Tulare County
Resource Management Agency
5961 S. Mooney Blvd.
Visalia, CA 93277

Reunión ID: 941 2263 30189

Contraseña: 907610

Teléfono: 1 669-900-9128

Contacto Para Preguntas


Susan Simon 559-624-7126

Jose Saenz (Español) 559-624-7102



¿CUALES SON SUS PREOCUPACIONES DE CARRETERA?

- Seguridad, congestión, velocidad del vehículo, farolas, paso de peatones.
- Baches, inundaciones, instalaciones de drenaje, pavimentación fuera de la carretera.
- Bordillo, alcantarilla, acera, rampas de bordillo.
- Transito y paradas de autobus escolar, carriles de bicicletas.



London Complete Streets 2021

Presented By:

Aaron Bock, Assistant Director

Chuck Przybyski, Planner IV

Resource Management Agency



June 17, 2021

London Complete Streets 2021

2


Project Funding

2020/2021 Tulare County Association of Governments
Sustainable Communities Planning Grant Complete Streets
\$140,708.

Project Communities include: Plainview, East Porterville, Paige
Moore Tract (Lindsay), and London.

London Complete Streets 2021

3



London Complete Streets 2021

4

Next
Public
Outreach

- Study Session 2: Thursday, July 8, 2021 at 6:00 pm

5

Questions



Aaron Bock

Tulare County RMA, Assistant Director
(559) 624-7050
ABock@tularecounty.ca.gov

Johnny Wong


Tulare County RMA, Chief Engineer
(559) 624-7170
jwong@tularecounty.ca.gov
(Pot hole questions)

Chuck Przybylski

Tulare County RMA, Planner IV
(559) 624-7000
CPrzybyl@tularecounty.ca.gov

Susan Simon

Tulare County RMA, Planner III
(559) 624-7126
ssimon@tularecounty.ca.gov



London Complete Streets 2021

Presented By:

Aaron Bock, Assistant Director

Chuck Przybyski, Planner IV

Resource Management Agency



July 8, 2021

London Complete Streets 2021

2

Project Funding

2020/2021 Tulare County Association of Governments
Sustainable Communities Planning Grant Complete Streets
\$140,708.

Project Communities include: Plainview, East Porterville, Paige
Moore Tract (Lindsay), and London.

London Complete Streets 2021

3



London Complete Streets 2021

4

Next Public Outreach

- Study Session 4: Thursday, July 22, 2021 at 6:00 pm
at the London Community Center located at 5750 Avenue
378, Dinuba, CA 93618

5

Questions



Aaron Bock

Tulare County RMA, Assistant Director
(559) 624-7050
ABock@tularecounty.ca.gov

Johnny Wong


Tulare County RMA, Chief Engineer
(559) 624-7170
jwong@tularecounty.ca.gov
(Pot hole questions)

Chuck Przybylski

Tulare County RMA, Planner IV
(559) 624-7000
CPrzybyl@tularecounty.ca.gov

Susan Simon

Tulare County RMA, Planner III
(559) 624-7126
ssimon@tularecounty.ca.gov



London Complete Streets 2021

Presented By:

Aaron Bock, Assistant Director

Chuck Przybyski, Planner IV

Resource Management Agency



July 22, 2021

London Complete Streets 2021

2


Project Funding

2020/2021 Tulare County Association of Governments
Sustainable Communities Planning Grant Complete Streets
\$140,708.

Project Communities include: Plainview, East Porterville, Paige
Moore Tract (Lindsay), and London.

London Complete Streets 2021

3



London Complete Streets 2021

4

Next
Public
Outreach

- Study Session 2: Thursday, July 8, 2021 at 6:00 pm

5

Questions



Aaron Bock

Tulare County RMA, Assistant Director
(559) 624-7050
ABock@tularecounty.ca.gov

Johnny Wong

Tulare County RMA, Chief Engineer
(559) 624-7170
jwong@tularecounty.ca.gov
(Pot hole questions)

Chuck Przybylski

Tulare County RMA, Planner IV
(559) 624-7000
CPrzybyl@tularecounty.ca.gov

Susan Simon

Tulare County RMA, Planner III
(559) 624-7126
ssimon@tularecounty.ca.gov

Legend

- Proposed Location
- Community of London
- County Boundary



WE WANT TO KNOW WHAT YOU THINK



CIRCLE YOUR "AREA" OF ROAD CONCERNS FOR LONDON ON THE BELOW MAP AND YOUR CONCERNS ON THE BELOW LIST

- Safety, congestion, vehicle speed, streetlights, pedestrian crossing.
- Potholes, flooding, drainage facilities, pave out of the roadway.
- Curb, gutter, sidewalk, curb ramps.
- Transit and school bus stops, bike lanes.

We also appreciate any notes you can make!

COMMUNITY VISIONING

COMPLETE STREETS PLANNING

PUBLIC MEETING

COMMUNITY INPUT NEEDED

Return to address below

Tulare County
Resource Management Agency
5961 S. Mooney Blvd.
Visalia, CA 93277

Questions Contact

Susan Simon 559-624-7126
Jose Saenz (Spanish) 559-624-7102



Legend


- Proposed Location
- Community of London
- County Boundary

stop @ Library never made

North Rd 57 to 378, 35 or 40 miles per hr

QUAD Race Track from Rd 60 N to 378 west to Rd 57 S to Rd 376 W to 60. AT LEAST 4 or 5 SQUADS AVE 378 @ Rd 58 STOP - CALIFORNIA style

68



London Calles Completas 2021

Presentacion por::

Aaron Bock, Assistant Director

Chuck Przybyski, Planner IV

Resource Management Agency



22 de Julio, 2021

London Calles Completas 2021

2

¿Qué es Calles Completas?

- La Ley de Calles Completas de California (AB 1358) requiere que todas las ciudades y condados identifiquen cómo proporcionar alojamiento de rutina a todos los usuarios de las carreteras, incluidos automovilistas, peatones, ciclistas, personas con discapacidades, personas mayores y usuarios del transporte público.
- Además, estas Políticas de calles completas, una vez aprobadas, pueden dar lugar a una adjudicación de fondos para la construcción de parte de TCAG o Caltrans para estas comunidades.
- Con ayuda y información de la comunidad, el condado diseña y planifica aceras, carriles para bicicletas y paradas de tránsito. Luego, cuando la financiación de la subvención esté disponible, ya habrá un plan de diseño disponible.
- Con el aporte de la comunidad, el condado diseña y planifica aceras, carriles para bicicletas y paradas de tránsito. Luego, cuando la financiación de la subvención esté disponible, ya habrá un plan de diseño disponible.
- El condado recibió una subvención de TCAG para diseñar estas características para varias comunidades, incluida Londres.

London Calles Completas 2021

3

Fondos de Proyecto

2020/2021 Tulare County Association of Governments Sustainable Communities Planning Grant Complete Streets \$140,708.

Las comunidades del proyecto incluyen: Plainview, East Porterville, Paige Moore Tract (Lindsay), and London.

London Calles Completas 2021

4

Complete Streets Definición

Calles Completas son carreteras diseñadas para acomodar de manera segura y cómoda a todos los usuarios, independientemente de su edad, capacidad o modo de transporte. Las consideraciones de diseño para la gestión de la conectividad y el acceso también se tienen en cuenta para los usuarios no motorizados de la instalación.

- Automovilistas
- Ciclistas
- Peatones
- Transporte público
- Socorristas de emergencia
- Camiones de carga y reparto.
- Adaptaciones para personas discapacitadas según lo exige la ADA.

London Calles Completas 2021

5

Complete Streets Definicion

La implementación del diseño de Complete Street se basa en si conecta las redes para todos los modos,

- Si mejora la funcionalidad para todos los usuarios,
- Si es apropiado dado el contexto circundante de la comunidad.

Como mínimo, una calzada de Complete Street incluye:

- Aceras y servicios de acera,
- Refugios e instalaciones de tránsito siempre que haya una ruta a lo largo del corredor, y
- Provisiones para instalaciones para bicicletas.

London Calles Completas 2021

6


Diseño

Cuando miramos una calle completa para el diseño, observamos:

- Acceso a las escuelas
- Paradas de autobús escolar
- Paradas de tránsito
- Acceso a las cuencas de aguas pluviales
- Usos comerciales
- Ancho de camino
- Conectividad entre los anteriores

London Calles Completas 2021

7



London Calles Completas 2021

8

Prioridades
Camino

Comunidad de London Calles completas :

- Avenue 378
- Kate Road

El plan de London y las prioridades :

- Pounce Road
- Road 58
- Avenue 377
- All roads

London Calles Completas 2021 - Survey

9

QUEREMOS SABER LO QUE PIENSA



EN EL MAPA DIBUJE UN CÍRCULO EN LA "ÁREA" DE PREOCUPACIÓN EN LAS CARRETERAS EN LONDON EN LAS PREOCUPACIONES DE LA LISTA DE ABAJO

- Seguridad, congestión, velocidad de vehículos, farola, paso de peatones.
- Baches, inundaciones, instalaciones de drenaje, pavimentar la carretera.
- Bordillo, alcantarilla, acera, rampas de bordillo.
- Paradas de tránsito y de autobús escolar, carriles de bicicletas.

¡También apreciamos cualquier comentario que pueda hacer!



VISIÓN COMMUNITARIA

PLANIFICACIÓN COMPLETA DE LA CALLE

REUNIÓN PÚBLICA

APORTE DE COMUNIDAD

Volver a la dirección

Tulare County
Resource Management Agency
5961 S. Mooney Blvd.
Visalia, CA 93277

Para preguntas contactar

Susan Simon 559-624-7126
Jose Saenz (Español) 559-624-7102



London Calles Completas 2021

10

Forma para
problemas
de
carreteras



(<http://tularecounty.ca.gov/>)

Tulare County Resource Management Agency

(/rma/)

Search



Home (/rma/) / Public Works (/rma/index.cfm/public-works/)
/ Roads (/rma/index.cfm/public-works/roads/)
/ Report a Problem (/rma/index.cfm/public-works/roads/report-a-problem/)

Report a Problem Related to Flooded Roads, Potholes, and Damaged or Missing Road Signs

To report a pothole, flooding, and missing or damaged road signs, call the County Road Yard nearest you. Click here for the locations and phone numbers (/rma/index.cfm/public-works/roads/roads-division/) to all road yards, use the form below, or call (559) 624-7000.

ROAD PROBLEM SUBMISSION FORM

Fill out the fields below to report a road problem. Please note that not all roads within the County of Tulare are under County jurisdiction.

Name

Phone Number

Problem *

Pothole



Road District *

District 1



Description *

11

Preguntas?



Aaron Bock

Tulare County RMA, Assistant Director
(559) 624-7050
ABock@tularecounty.ca.gov

Johnny Wong


Tulare County RMA, Chief Engineer
(559) 624-7170
jwong@tularecounty.ca.gov
(Pot hole questions)

Chuck Przybylski

Tulare County RMA, Planner IV
(559) 624-7000
CPrzybyl@tularecounty.ca.gov

Susan Simon

Tulare County RMA, Planner III
(559) 624-7126
ssimon@tularecounty.ca.gov



London Complete Streets 2021

Presented By:

Aaron Bock, Assistant Director

Chuck Przybyski, Planner IV

Resource Management Agency



July 22, 2021

London Complete Streets 2021

2

What is Complete Streets

- The California Complete Streets Act (AB 1358) requires all cities and counties to identify how to provide for routine accommodation of all roadway users, including motorists, pedestrians, bicyclists, people with disabilities, seniors, and users of public transportation.
- In addition, these Complete Street Policies, once approved, can lead to an award of construction funding from TCAG or Caltrans for these communities.
- With input from the community, the county designs and plans for sidewalks, bike lanes, transit stops. Then, when grant funding becomes available, there is a design plan already available.
- Once all the plans are completed, the plans will go before the Board of Supervisors for adoption.
- The County received a grant from TCAG to design these features for several communities, including London.

London Complete Streets 2021

3

Project Funding

2020/2021 Tulare County Association of Governments
Sustainable Communities Planning Grant Complete
Streets \$140,708.

Project Communities include: Plainview, East Porterville,
Paige Moore Tract (Lindsay), and London.

London Complete Streets 2021

5

Complete Streets Definition

Complete Streets are roadways designed to safely and comfortably accommodate all users, regardless of age, ability or mode of transportation. Design considerations for connectivity and access management are also taken into account for non-motorized users of the facility.

- Motorists
- Cyclists
- Pedestrians
- Public transportation
- Emergency responders
- Freight and delivery trucks.
- Accommodations for disabled persons as required by the ADA.

London Complete Streets 2021

5

Complete Streets Definition

Implementation of Complete Street design is based on whether it connects the networks for all modes,

- Whether it improves the functionality for all users,
- Whether it is appropriate given the surrounding context of the community.

At a minimum, a Complete Street roadway includes:

- Sidewalks and sidewalk amenities,
- Transit shelters and facilities whenever there is a route along the corridor, and
- Provisions for bicycle facilities.

London Complete Streets 2021

7

Design

When looking at a complete street for design, we look at:

- Access to schools
- School bus stops
- Transit stops
- Access to storm water basins
- Commercial Uses
- Road width
- Connectivity between the above

London Complete Streets 2021

4



London Complete Streets 2021

6

Road Priorities

Community of London Road Priorities:

- Avenue 378
- Kate Road

London Community Plan Road Priorities

- Avenue 377
- Pound Road
- Road 58

London Complete Streets 2021 - Survey

8

WE WANT TO KNOW WHAT YOU THINK



CIRCLE YOUR "AREA" OF ROAD CONCERNS FOR LONDON ON THE BELOW MAP AND YOUR CONCERNS ON THE BELOW LIST

- Safety, congestion, vehicle speed, streetlights, pedestrian crossing.
- Potholes, flooding, drainage facilities, pave out of the roadway.
- Curb, gutter, sidewalk, curb ramps.
- Transit and school bus stops, bike lanes.

We also appreciate any notes you can make!



COMMUNITY VISIONING

COMPLETE STREETS PLANNING

PUBLIC MEETING

COMMUNITY INPUT NEEDED

Return to address below

Tulare County
Resource Management Agency
5961 S. Mooney Blvd.
Visalia, CA 93277

Questions Contact

Susan Simon 559-624-7126
Jose Saenz (Spanish) 559-624-7102



London Complete Streets 2021

9

Road Problem Submission Form



(<http://tularecounty.ca.gov/>)

Tulare County Resource Management Agency

(/rma/)

Search



Home (/rma/) / Public Works (/rma/index.cfm/public-works/)
/ Roads (/rma/index.cfm/public-works/roads/)
/ Report a Problem (/rma/index.cfm/public-works/roads/report-a-problem/)

Report a Problem Related to Flooded Roads, Potholes, and Damaged or Missing Road Signs

To report a pothole, flooding, and missing or damaged road signs, call the County Road Yard nearest you. Click here for the locations and phone numbers (/rma/index.cfm/public-works/roads/roads-division/) to all road yards, use the form below, or call (559) 624-7000.

ROAD PROBLEM SUBMISSION FORM

Fill out the fields below to report a road problem. Please note that not all roads within the County of Tulare are under County jurisdiction.

Name

Phone Number

Problem *

Pothole



Road District *

District 1



Description *

10

Questions



Aaron Bock

Tulare County RMA, Assistant Director
(559) 624-7050
ABock@tularecounty.ca.gov

Johnny Wong

Tulare County RMA, Chief Engineer
(559) 624-7170
jwong@tularecounty.ca.gov
(Pot hole questions)

Chuck Przybylski

Tulare County RMA, Planner IV
(559) 624-7000
CPrzybyl@tularecounty.ca.gov

Susan Simon

Tulare County RMA, Planner III
(559) 624-7126
ssimon@tularecounty.ca.gov

Next Steps

- Goshen last public outreach meeting, Tuesday, April 20, 2021 at 6:00 pm
- East Porterville – April 15th, April 29th, and May 13th
- Matheny Tract – April 13th, April 27th and May 11th
- Paige Moore (Lindsay) – April 22nd, May 6th and May 20th
- West Goshen – May 27th, June 10th, and June 24th
- London - June 3rd, June 17th, and July 8th
- Mr. Winton working on 30% design plan and estimate for Plainview

Adjourn

Minutes Complete Streets staff meeting

April 13, 2021

Attendees:

Aaron Bock	Assistant Director
Hernan Beltran	Chief Engineer
Johnson Vang	Engineer III
Mike Winton	Engineer IV
Eliza Gonzalez	Administrative Aide
Chuck Przybylski	Planner IV
Susan Simon	Planner III
Julian Sanchez	Engineer I

Where we are:

- Mr. Winton has received topo's for Plainview
- Mr. Winton working on 30% plans and estimate for Plainview
- East Tulare Villa public outreach completed April 8, 2021
- Mr. Winton ordered topo's for East Tulare Villa (\$10,000)
- Budget information has been obtained from Fiscal. Caltran's budget is under grant and TCAG is considered under budget line Roads.
- Matheny Tract held first zoom meeting 4/13/2021 Blanca Escobedo, Leadership, participated and five (5) community members attended (translation required)
- East Porterville first zoom meeting 4/15/2021, one community member attended.
- Mr. Vang completed maps for West Goshen and London

Next Steps:

- Goshen last Zoom outreach 4/20/2021
 - Spreadsheet for Goshen outreach
- Lindsay First Zoom outreach 4/22/2021
 - Sierra View
 - Questions regarding Rule 28 (utility credit) in exchange?

Wrap-up

Next staff meeting, April 27, 2021, at 2:30 to 3:30 pm



Complete Streets Staff Meeting Agenda

April 20, 2021

Where We Are:

- Received maps for London and West Goshen from Mr. Vang
- Goshen final public outreach Tuesday, April 20, 2021 at 6:00 pm
- Paige Moore (Lindsay) public outreach Thursday, April 22, 2021 at 6:00 pm (need Translation)
- Mr. Winton has received Plainview topo's.
- Mr. Winton ordered East Tulare Villa topo's (approximately \$10,000)
- Comment Spreadsheets for Goshen (see attached)

Reports:

- Susan Simon
- Johnson Vang
- Michael Winton

Next Steps

- East Porterville – April 29th, and May 13th
- Matheny Tract – April 27th, and May 11th
- Paige Moore (Lindsay) – April, 29, May 6th and May 20th
- West Goshen – May 27th, June 10th, and June 24th
- London - June 3rd, June 17th, and July 8th
- Mr. Winton working on 30% design plan and estimate for Plainview
- Next Staff meeting, April 27th at 2:30 – 3:30 pm
- **Adjourn**

Minutes Complete Streets staff meeting

April 20, 2021

Attendees:

Hernan Beltran Herrera	Chief Engineer
Johnson Vang	Engineer III
Mike Winton	Engineer IV
Chuck Przybylski	Planner IV
Susan Simon	Planner III

Where we are:

- Mr. Winton has received topo's for Plainview
- Mr. Winton working on 30% plans and estimate for Plainview
- Mr. Przybylski to discuss East Tulare Villa budget with Mr. Bock (approximately \$10,000 for topo's)
- Goshen fourth zoom meeting held 4/20/2021, fourteen people attended.
- Lindsay first zoom meeting held 4/22/2021 need translator.
- East Porterville (side meeting with Mr. Beltran Herrera, Mr. Vang, Mr. Przybylski, and Ms Simon)
- Matheny Tract design layouts and cost estimates completed

Next Steps:

- East Porterville second zoom outreach meeting 4/29/2021.
- Matheny Tract second zoom outreach 4/27/2021
-

Wrap-up

Next staff meeting, May 4, 2021, at 2:30 to 3:30 pm



Complete Streets Staff Meeting Agenda

April 27, 2021

Where We Are:

- Goshen public outreach completed.
- Matheny Tract second public outreach Tuesday, April 27, 2021 at 6:00 pm
- East Porterville third public outreach Thursday, April 29, 2021 at 6:00 pm
- Paige Moore (Lindsay) second public outreach Thursday, May 6, 2021 at 6:00 pm
- Mr. Winton has received Plainview topo's.
- Mr. Przybylski to check with Mr. Bock regarding budget for East Tulare Villa topo's (approximately \$10,000)

Reports:

- Johnson Vang
- Michael Winton

Next Steps

- East Porterville –April 29th, and May 13th
- Matheny Tract –April 27th, and May 11th
- Paige Moore (Lindsay) – May 6th and May 20th
- West Goshen – May 27th, June 10th, and June 24th
- London - June 3rd, June 17th, and July 8th
- Mr. Winton working on 30% design plan and estimate for Plainview
- Next Staff meeting, May 4th, at 2:30 – 3:30 pm
- **Adjourn**



Complete Streets Staff Meeting Agenda

May 4, 2021

Where We Are:

- Goshen public outreach completed.
- East Tulare Villa public outreach completed.
- Matheny Tract last public outreach Tuesday, May 11, 2021 at 6:00 pm
- East Porterville last public outreach Thursday, May 13, 2021 at 6:00 pm
- Paige Moore (Lindsay) second public outreach Thursday, May 6, 2021 at 6:00 pm
- Mr. Winton has received Plainview topo's.

Reports:

- Susan Simon (preparing mailing West Goshen and London public outreach)
- Johnson Vang
- Michael Winton

Next Steps

- East Porterville – May 13th
- Matheny Tract – May 11th
- Paige Moore (Lindsay) – May 6th and May 20th
- West Goshen – May 27th, June 10th, and June 24th
- London - June 3rd, June 17th, and July 8th
- Mr. Winton working on 30% design plan and estimate for Plainview
- Next Staff meeting, May 11th, at 2:30 – 3:30 pm
- **Adjourn**

Minutes Complete Streets staff meeting

May 5, 2021

Attendees:

Aaron Bock	Assistant Director
Johnson Vang	Engineer III
Mike Winton	Engineer IV
Chuck Przybylski	Planner IV
Susan Simon	Planner III
Eliza Gonzalez	Administrative Aide

Where we are:

- Lindsay second zoom meeting held Thursday, May 6, 2021.
- Matheny Tract final zoom outreach 5/11/2021
 - Ms. Simon and Mr. Przybylski out of office
 - Caltrans will be attending.
 - Presentation to include information from Matheny Tract Adaptation Plan
 - Beautification with trees along Beacon, Addie, Matheny, Prine.
 - Choose two roadways for complete streets design.
 - Mr. Vang and Mr. Przybylski to visit Matheny Tract and take pictures.
- East Porterville third zoom meeting Thursday, May 13, 2021 at 6:00 pm.
 - Ms Simon out of office and Mr. Saenz will be opening meeting and translating.

Next Steps:

- Sending out flyers to West Goshen and London communities.

Wrap-up

Next staff meeting, May 11, 2021, at 2:30 to 3:30 pm



Complete Streets Staff Meeting Agenda

May 18, 2021

Where We Are:

- This week's public outreach meeting with Lindsay on Thursday, May 20, 2021 at 6:00 pm
- TCAG's public outreach completed (Plainview and East Porterville).
- Caltrans public outreach completed (Goshen, East Tulare Villa and Matheny Tract).
- West Goshen public outreach flyers mailed May 18, 2021.
- London public outreach flyers mailed May 18, 2021.
- Plainview topo's received.
- East Tulare Villa topo's ordered.
- Matheny Tract topo's completed.

Reports:

- Susan Simon
- Johnson Vang
- Michael Winton

Next Steps

- Paige Moore (Lindsay) –May 20th
- West Goshen – May 27th, June 10th, and June 24th
- London - June 3rd, June 17th, and July 8th
- Mr. Winton working on 30% design plan and estimate for Plainview
- Next Staff meeting, May 24th, at 2:30 – 3:30 pm
- **Adjourn**

Minutes Complete Streets staff meeting

May 18, 2021

Attendees:

Johnson Vang	Engineer III
Mike Winton	Engineer IV
Chuck Przybylski	Planner IV
Susan Simon	Planner III
Eliza Gonzalez	Administrative Aide
Elisabeth Ramirez	EH Office Assistant II

Where we are:

- Lindsay last zoom meeting Thursday, May 20, 2021.
- Public Outreach completed:
 - Plainview
 - East Porterville
 - Matheny Tract
 - Goshen
 - East Tulare Villa
- West Goshen flyers/Surveys mailed.
- London flyers/surveys mailed.
- Topo's received:
 - Plainview
 - East Tulare Villa
- Design completed (I need copies of this)
 - Matheny Tract

Next Steps:

- West Goshen – May 27th, June 19th, and June 24th.
- London – June 3rd, June 17th, and July 8th.

Wrap-up

Next staff meeting, May 25, 2021, from 2:30 to 3:30 pm



Complete Streets Staff Meeting Agenda

May 25, 2021

Where We Are:

- This week's public outreach meeting with West Goshen on Thursday, May 27, 2021 at 6:00 pm
- TCAG's public outreach completed (Plainview, East Porterville, and Lindsay).
- Caltrans public outreach completed (Goshen, East Tulare Villa and Matheny Tract).
- West Goshen public outreach flyers mailed May 18, 2021.
- London public outreach flyers mailed May 18, 2021.
- Topo's received.
 - Plainview
 - East Tulare Villa
- Complete design
 - Matheny Tract

Reports:

- Susan Simon
- Johnson Vang (last week)
- Michael Winton

Next Steps

- West Goshen – May 27th, June 10th, and June 24th
- London - June 3rd, June 17th, and July 8th
- Next Staff meeting, June 1st from 2:30 – 3:30 pm
- **Adjourn**

Minutes Complete Streets staff meeting

May 25, 2021

Attendees:

Johnson Vang	Engineer III
Chuck Przybylski	Planner IV
Susan Simon	Planner III
Eliza Gonzalez	Administrative Aide
Elizabeth Ramirez	EH Office Assistant II

Where we are:

- West Goshen Thursday 27th 2021 at 6:00pm.
- Public Outreach completed:
 - Plainview
 - East Porterville
 - Matheny Tract
 - Goshen
 - East Tulare Villa
- Topos received.
 - Plainview
 - East Tulare Villa
- Design completed.
 - Matheny Tract
- London Kate/Ave 378
- Update on schedule to stay on track.

Next Steps:

- Matheny Tract
 - Mike to turn in
- West Goshen – May 27th, June 19th, and June 24th.
- London – June 3rd, June 17th, and July 8th.

Wrap-up

Next staff meeting, June 8, 2021, from 2:30 to 3:30 pm



Complete Streets Staff Meeting Agenda

June 8, 2021

Where We Are:

- This week's public outreach meeting with West Goshen on Thursday, June 10, 2021 at 6:00 pm
- TCAG's public outreach completed (Plainview, East Porterville, and Lindsay).
- Caltrans public outreach completed (Goshen, East Tulare Villa and Matheny Tract).
- Topo's received.
 - Plainview
 - East Tulare Villa
- Complete design
 - Matheny Tract
- Designs (30%) for TCAG (Plainview, Lindsay, East Porterville, and London) will be completed by July 31, 2021.
- TCAG Complete Streets Project will go to BOS on consent calendar in August.

Reports:

- Johnson Vang (welcome back)
- Michael Winton

Next Steps

- West Goshen – June 10th, and June 24th
- London - June 17th, and July 8th
- Next Staff meeting, June 15th from 2:30 – 3:30 pm
- **Adjourn**

Minutes Complete Streets Staff Meeting

June 8, 2021

Charles Przybylski	Planner IV
Susan Simon	Planner III
Eliza Gonzalez	Administrative Aide
Elizabeth Ramirez	EH Office Assistant II
Michael Winton	Engineer IV
Johnson Vang	Engineer III

Start time: 2:30 pm

Where we are:

- West Goshen Thursday, June 10, 2021, at 6pm
- Goshen attendee received more flyers and surveys
- London meeting last week no attendees
- Porterville, Plainview and Lindsay are all complete
- Topos received
 - Plainview
 - East Tulare Villa
- Complete design for Matheny
- Still waiting on the 30% for Plainview, Lindsay, East Porterville and London.
 - Due date of July 31,2021
- TCAG Complete Streets project to be presented in August to the Board.
 - Plainview
 - Porterville
 - Lindsay
 - London

Reports:

- Mike Winton-
- Johnson Vang-Follow up on food donations

Next step:

- Plans to be completed by end of July
- West Goshen June 10th and June 24th
- London June 17th and July 8th
- Next staff meeting, June 15th from 2:30pm – 3:30 pm

Adjourned: 3:45 pm



Complete Streets Staff Meeting Agenda

June 15, 2021

Where We Are:

- This week's public outreach meeting with London on Thursday, June 10, 2021 at 6:00 pm
- TCAG's public outreach completed (Plainview, East Porterville, and Lindsay).
- Caltrans public outreach completed (Goshen, East Tulare Villa and Matheny Tract).
- Planning received 30% design.
 - Plainview
- Engineering received Topo's.
 - East Tulare Villa
- Complete design
 - Matheny Tract
- Designs (30%) for TCAG (Plainview, Lindsay, East Porterville, and London) will be completed by July 31, 2021.
- TCAG Complete Streets Project will go to BOS on consent calendar in August.

Reports:

- Michael Winton

Next Steps

- West Goshen – June 24th
- London - June 17th, and July 8th
- Next Staff meeting, June 29th from 2:30 – 3:30 pm
- **Adjourn**



Complete Streets Staff Meeting Agenda

June 29, 2021

Where We Are:

- Last public outreach meeting with London on Thursday, July 8, 2021 at 6:00 pm
- TCAG's public outreach completed (Plainview, East Porterville, and Lindsay).
- Caltrans public outreach completed (Goshen, East Tulare Villa, Matheny Tract, and West Goshen).
- Planning received 30% design.
 - Plainview
- Engineering received Topo's.
 - East Tulare Villa
- Complete design
 - Matheny Tract
- Designs (30%) for TCAG (Plainview, Lindsay, East Porterville, and London) will be completed by July 31, 2021.
- TCAG Complete Streets Project will go to BOS on consent calendar in August.

Reports:

- Michael Winton

Next Steps

- London - July 8th
- Next Staff meeting, July 13th from 2:30 – 3:30 pm
- **Adjourn**

Minutes Complete Streets Staff Meeting

June 29, 2021

Charles Przybylski	Planner IV
Hernan Beltran Herrera	Chief Engineer
Eliza Gonzalez	Administrative Aide
Elizabeth Ramirez	EH Office Assistant II
Michael Winton	Engineer IV
Juliana Sanchez	Engineer I

Start time: 2:30 pm

Where we are:

- London meeting last week no attendees
- London Topo's sent off before July 8th
- Porterville, Plainview and Lindsay are all complete
- Caltrans public outreach (Goshen, East Tulare Villa, Matheny Tract, and West Goshen no changes
- August depending on Topo's should have 6 of 8 communities complete
- Topos received
 - East Tulare Villa
 - Planning received 30% design for Plainview
- Complete design for Matheny
- Still waiting on the 30% for Lindsay, East Porterville and London.
 - Due date of July 31,2021
- TCAG Complete Streets project to be presented in August to the Board.
 - Plainview
 - Porterville
 - Lindsay
 - London

Reports:

- Mike Winton Tulare Villa 30% complete Engineers received Topo's

Next step:

- Plans to be completed by end of July
- London June July 8th Last meeting
- All 8 of the communities to be completed by November
- Topo's East Porterville Late July and Lindsay late August
- Next staff meeting, July 13th from 2:30 pm-3:30 pm

Adjourned: 3:30 pm



Complete Streets Staff Meeting Agenda

July 13, 2021

Where We Are:

- London Complete Streets in person held at the Hodges Community Center in London on July 22nd at 6:00 pm.
- London Flyers for in person public outreach mailed July 12, 2021.
- TCAG's public outreach completed (Plainview, East Porterville, and Lindsay).
- Caltrans public outreach completed.
- Planning received 30% design.
 - Plainview
- Engineering received Topo's.
 - East Tulare Villa
- Complete design
 - Matheny Tract
- Designs (30%) for TCAG (Plainview, Lindsay, East Porterville, and London) will be completed by July 31, 2021.
- TCAG Complete Streets Project will go to BOS on consent calendar in August.

Reports:

- Eliza Gonzalez
- Michael Winton

Next Steps

- London - July 22nd to be held in person at the Hodges Community Center in London located at 5750 Avenue 378, Dinuba at 6:00 pm.
- **Adjourn**

Minutes Complete Streets Staff Meeting

July 13, 2021

Charles Przybylski	Planner IV
Joe Cordova	Planner III
Eliza Gonzalez	Administrative Aide
Elizabeth Ramirez	EH Office Assistant II

Start time: 2:30 pm

Where we are:

- London meeting last week no attendees
- London Topo's sent off before July 27th
- Porterville, Plainview and Lindsay are all complete
- Caltrans public outreach (Goshen, East Tulare Villa, Matheny Tract, and West Goshen no changes
- August depending on Topo's should have 6 of 8 communities complete
- Topos received
 - East Tulare Villa
 - Planning received 30% design for Plainview
- Complete design for Matheny
- Still waiting on the 30% for Lindsay, East Porterville and London.
 - Due date of September 31,2021
- TCAG Complete Streets project to be presented in August to the Board.
 - Plainview
 - Porterville
 - Lindsay
 - London

Reports:

- Eliza Gonzales Tulare Villa 30% complete Engineers received Topo's and Matheny Track is complete.

Next step:

- Plans to be completed by end of September
- London meeting at the community center in person Last meeting
- All 8 of the communities to be completed by November
- Topo's East Porterville Late July and Lindsay late August
- Next staff meeting, July 20 from 2:30 pm-3:30 pm For review of in person meeting at London Community Center

Adjourned: 2:45pm



Complete Streets Staff Meeting Agenda

July 20, 2021

Where We Are:

London Complete Streets in person held at the Hodges Community Center in London on July 22nd at 6:00 pm.

- London Flyers for in person public outreach mailed July 12, 2021.
- Flyers placed at Community Center and two stores within London.
- Review of presentation
- Equipment required for presentation:
 - Projector
 - Electric cord
 - Computer
 - screen
- Water
- Pencils
- Maps
- Surveys

Adjourn

Minutes Complete Streets Staff Meeting

July 13, 2021

Charles Przybylski	Planner IV
Joe Cordova	Planner III
Eliza Gonzalez	Administrative Aide
Elizabeth Ramirez	EH Office Assistant II

Start time: 2:30 pm

Where we are:

- London meeting last week no attendees
- London Topo's sent off before July 27th
- Porterville, Plainview and Lindsay are all complete
- Caltrans public outreach (Goshen, East Tulare Villa, Matheny Tract, and West Goshen no changes
- August depending on Topo's should have 6 of 8 communities complete
- Topos received
 - East Tulare Villa
 - Planning received 30% design for Plainview
- Complete design for Matheny
- Still waiting on the 30% for Lindsay, East Porterville and London.
 - Due date of September 31,2021
- TCAG Complete Streets project to be presented in August to the Board.
 - Plainview
 - Porterville
 - Lindsay
 - London

Reports:

- Eliza Gonzales Tulare Villa 30% complete Engineers received Topo's and Matheny Track is complete.

Next step:

- Plans to be completed by end of September
- London meeting at the community center in person Last meeting
- All 8 of the communities to be completed by November
- Topo's East Porterville Late July and Lindsay late August
- Next staff meeting, July 20 from 2:30 pm-3:30 pm For review of in person meeting at London Community Center

Adjourned: 2:45pm

Complete Streets Program & Policy Plans for Plainview, Page- Moore, East Porterville and London



November 10, 2021

Presented by the

Tulare County Resource Management Agency

Paid for by SB1 Funds

Through the Tulare County Association of Governments



Results (2014 to present)

- Overall, applied for and received \$700,000 in grant funding from TCAG (\$500K) and Caltrans (\$200K) .
- 17 communities completed with 76 roadways planned
- Currently working on 8 communities with 7 roadways planned
- Avg. \$30,000 per program/design including:
 - Outreach
 - Project Selection Process (internal & external)
 - Site Survey
 - 30% Design (Plans and Specs)
 - Estimates
 - Individual Program Documents
 - Updating GPA to Circulation Elements
- Resulted in 36 selections for further Adaptive Transportation Program ATP construction funding
- Resulted in 15 awards for construction funding estimated at over \$15 million in construction.
- .046 Cost / Benefit Ratio so 4% of every major community road project (with no additional cost to county for planning, as 10% matches are programmed into general plan funding)



Pixley Main Street

So why Complete Streets

- Led to the Countywide ATP
- Creates sidewalks, which lower pedestrian accidents up to 70% / avg. cost per accident is \$185,000
- Creates bus stops (updated TCAT's map for dozens of new stops and new routes)
- Created several safe school drop off zones with the "blinky lights"
- Increases signage and signalization (so increases road safety)
- Creates gutters which focuses drainage, so under "safe routes to schools" children don't have to walk in the flooded roads and roads aren't a hazard for drivers
- Fixes major roadways that attracts / keeps businesses
- Helps locate potholes
- Provides the mechanisms to fix major potholes
- Makes the public aware of the maintenance programs in their communities
- Currently, collaborating with TCAG and Caltrans for road projects tied to the first road diet project in Cutler Orosi on SR 63



Completed Projects

4

<i>Phase I</i>	<i>Complete Streets Policy Plans (2014-15)</i>	30% Design	Grant App	Grant Award	ATP Cycle 1	ATP Cycle 2	ATP Cycle 3	ATP Cycle 4
<i>Community</i>	<i>Project Name/Street Section</i>							
Traver	Complete Streets Policy Plan							
	Sixth Street – SR 99 to Merritt Dr. (30% design) \$1.66M	✓						
	Merritt Drive – Burke Drive to Canal (30% design) \$1.30M	✓				✓		✓
	Church Street – Kitchner to Jacob							
	Bullard Street – Burke to Baker							
	Jacob Street – Burke to Canal	✓	✓	✓		✓		
Goshen	Complete Streets Policy Plan							
	Betty Drive – Road 67 to Robinson Street (30% design) \$1.24K	✓						
	Goshen Ave – Commercial Road to Road 76 (30 % design) \$4.67M	✓						
	Effie Drive – Road 76 to Goshen Ave							
	Harvest Ave – Road 64 to Road 66							
	Road 76 – Avenue 304 to Avenue 312							
	AVE 303 – SR-99 to Effie Dr		✓	✓				
Pixley	Complete Streets Policy Plan							
	Court Street – Main Street to School Street (30% design)	✓	✓	✓				
	Main Street – Court Street to Terra Bells (30% design)	✓	✓	✓		✓		
	Center Street – Court Street to Terra Bella							
	Elm Street – Court Street to Terra Bella							
	Davis Avenue – Elm and Ashe							




Phase II	Complete Streets Policy Plans (2014-16)	30% Design	Grant App	Grant Award	ATP Cycle 1	ATP Cycle 2	ATP Cycle 3	ATP Cycle 4
Community	Project Name/Street Section							
Strathmore	Complete Streets Policy Plan							
	Avenue 198 – Orange Belt to Road 230 (30% design)	✓					✓	✓
	Orange Belt Drive – Avenue 196 to Avenue 198 (30% design)	✓						
	Avenue 196 – Orange Belt Drive to Road 230		✓	✓				
	Road 230 – Avenue 196 to Avenue 198							
	Meredith – Ward to Avenue 194							
Earlimart	Complete Streets Policy Plan							
	State Street – Avenue 48 to Ave 56 (30% design)	✓					✓	
	Washington Avenue – Road 128 to Elm Rd (30% design)	✓	✓	✓		✓	✓	
	Church Street – Armstrong Ave to Ave 56					✓	✓	
	School Avenue – Church street to Elm Rd					✓		
Tipton	Complete Streets Policy Plan							
	Evans Road – Avenue 152 to SR 190 (30% design)	✓					✓	✓
	Woods Avenue – Thompson Road to Newman Road (30% design)	✓						
	Klindera Overcrossing of SR 99							
	Burnett Road – SR 190 to Avenue 152							
	Avenue 152							
Cutler	Complete Streets Policy Plan							
	George Rd/2nd Drive – Avenue 407 to SR 63 (30% design)	✓					✓	✓
	Avenue 408 – Road 124 to SR 63 (30% design)	✓						
	Railroad Drive – SR 63 to Robert Rd							
	First Drive – SR 63 to Road 124							
Orosi	Complete Streets Policy Plan							
	Avenue 416 – SR 63 to Road 140 (30% design)	✓	✓	✓			✓	✓
	Avenue 413 – Road 124 to SR 63 (30% design)	✓						
	Avenue 419							
	Avenue 416 – SR 63 to Dinuba		✓	✓				
	Road 130							
Ducor	Road 124							
	Complete Streets Policy Plan							
	Avenue 56 – SR 65 to the Elementary School (30% design)	✓					✓	
	Road 236 – Ducor to Terra Bella ; Class II Bike Lane (30% design)	✓						
	Parsons Avenue – Avenue 58 to Carlisle Road							
	Dennis Road – Avenue 55 to Parsons Avenue							
Terra Bella	Road 234 – Avenue 56 to Owen Avenue							
	Complete Streets Policy Plan							
	Avenue 95 – SR 65 to Road 236 (30% design)	✓	✓	✓				
	Road 237 – Avenue 96 to Avenue 92							
	Road 236 (Orange Belt) – Trailer Park to Avenue 88							
	Road 238 – Avenue 95 to Avenue 92							
	Avenue 94 – Road 236 to Road 238							

Phase III	Complete Streets Policy Plans (2016-17)	30% Design	Grant App	Grant Award	ATP Cycle 1	ATP Cycle 2	ATP Cycle 3	ATP Cycle 4
Community	Project Name/Street Section							
Alpaugh	Complete Streets Policy Plan							
	Avenue 53/Church – Knox Road to Ellis Road (30% design-sidewalk)	✓			✓	✓	✓	
	Road 38/Tule Road – Church Ave to Park Ave (30% design-sidewalk)	✓			✓	✓	✓	
	Avenue 54/Center – Tule Rd to Wilbur Rd (30% design-sidewalk)	✓	✓	✓	✓	✓	✓	✓
	Ellis Road – Church Ave to Center Ave (30% design-sidewalk)	✓			✓	✓	✓	
Allensworth	Complete Streets Policy Plan							
	Avenue 32 – Young Road to Road 84							
	Avenue 36 – Young Road to Avenue 84							
	Avenue 24 – Road 84 to Road 80							
	Avenue 28 – Road 80 to Road 84							
	Road 84 – Stowe Ave to Avenue 24		✓	✓				
	Young Road – Ave 36 to Allensworth Elementary (30% design)	✓	✓	✓			✓	
East Orosi	Complete Streets Policy Plan							
	Ave 418 – Road 139 to Road 140							
	Ave 416 – SR 63 to Road 140							
	Road 140/Lone Rd – Ave 416 to Ave 419 (30% design)	✓						
	Ave 419 – Road 139 to Road 140							
Ivanhoe	Complete Streets Policy Plan							
	Road 160 – Jasmine Ave to Ave 332 (30% design)	✓						✓
	Road 159 – Ave 328 to Ave 332 (30% design)	✓	✓	✓				
	Avenue 328 – Road 56 to Road 160							
	Road 156 – Ave 328 to Ave 332							
	Jasmine – Road 56 to Road 160							
Poplar	Complete Streets Policy Plan							
	Ave 145 – Road 190 to Road 193 (30% design)	✓						✓
	Kilroy – Ave 145 to Ave 146							
	Tobias – Dead End at Ave 144 to Ave 146							
	Road 192 – Ave 144 to Ave 148		✓	✓				
	Road 191 – Ave 145 to Ave 148							
Woodville	Complete Streets Policy Plan							
	Road 168 – Woodville Elementary School to Ave 168 (30% design)	✓	✓	✓		✓	✓	
	Ave 167 – Road 164 to Road 168						✓	
	Ave 169 – Road 164 to Road 168							
Three Rivers	Complete Streets Policy Plan (Pending 2018)							
	Candidate Segment SR 198 (Old Three Rivers Rd. to Eggers Dr. 30% design including Class II Bike Project)							

****Completed as of 5/24/2021**

Complete Streets Policy Plans
TCAG

Community	Project Name/Street Section
Plainview	Complete Streets Policy Plan
	Road 196 from north of Avenue 196 to Avenue 194 <ul style="list-style-type: none"> • Curb • Gutter • Sidewalks
	Road 196 from north of Avenue 196 to Avenue 194 <ul style="list-style-type: none"> • Pedestrian crossing enhancements • Radar feedback signs
	Road 196 from north of Avenue 196 to Avenue 194 <ul style="list-style-type: none"> • Transit facility (school/transit bus stops and shelters)
Page-Moore Lindsay	Complete Streets Policy Plan
	Bound by Lindsay High School to the east and Lincoln Elementary School to the west.
	*Avenue 232 - southern boundary of Page-Moore Tract already has complete Streets including curb, gutter, and sidewalk.
	*Scattered curb, gutter, and sidewalk throughout the community
East Porterville	Complete Streets Policy Plan
	Sidewalk along the segment of Orange Avenue between Leggett and Doyle Elementary
London	Complete Streets Policy Plan
	Road 58 – North/South and Kate Road
	East/west Avenue 378 corridor
	Transit and school bus stops should be upgraded (top priority)



Existing Conditions

9



Plainview



East Porterville



Paige-Moore Tract



West Goshen



London



Matheny Tract

Public Outreach Schedule


10

MONTH	MONDAY	PROJECT	TUESDAY	PROJECT	WEDNESDAY	PROJECT	THURSDAY	PROJECT
February	22		23		24		25	Goshen
March	1		2		3		4	East Tulare Villa
	8		9		10		11	Goshen
	15		16		17		18	East Tulare Villa
	22		23		24		25	Goshen
April							1	N/A
	5		6		7		8	West Goshen
	12		13	East Tulare Villa	14		15	Matheny Tract
	19		20		21		22	West Goshen
	26		27		28		29	Matheny Tract
May	3		4	Lindsay	5		6	West Goshen
	10		11		12		13	Matheny Tract
	17		18	Lindsay	19		20	East Porterville
	24	holiday	25		26		27	London
June			1		2		3	East Porterville
	7		8	Lindsay	9		10	London
	14		15		16		17	East Porterville
	21		22		23		24	London
	28		29		30			


London Complete Streets July 22, 2021 Hodges Community Center, London

11






SIERRA VIEW ST
206+91.69 TO 207+26.73
210+46.73 TO 212+51.28
213+43.28 TO 215+76.29
216+55.29 TO 218+97.65



SIERRA VIEW ST
201+26.06 TO 205+31.68



LAFAYETTE AVE
504+70.22 TO 624+75.55

LEGEND







- HOT MIX ASPHALT
- AGGREGATE BASE
- PROPOSED CONCRETE
- GRIND & REFACE
- EXISTING CONCRETE

TYPICAL STRUCTURAL SECTIONS

- 20-YEAR DESIGN
- 2" HOT MIX ASPHALT (TYPE A)
- 1" GLASS 2 AGGREGATE BASE, 90% COMPACTION
- 0.2" COMPACTED NATIVE SOIL COMPACTION
- MINOR CONCRETE, BARRIER TYPE, COMPACTED NATIVE
- CONCRETE MEDIAN, 4" THICK TYPICAL
- 0.2" GRIND & REFACE (TYPE A MMA)

NOTES

- ALL CONSTRUCTION SHALL BE INSIDE OF COUNTY RIGHT OF WAY AND REQUIRED BY ME.
- SEE PLAN SHEET FOR EXIST LOCATIONS OF DRAINAGE.
- GRADE AREA BEHIND SIERRA VIEW TO PROVIDE SMOOTH TRANSITION WHEN R/W. THIS IS INCLUDED IN THE PAYMENT FOR FINISHING ROADWAY.



30% SUBMITTAL
PRELIMINARY, NOT
FOR CONSTRUCTION

30% SUBMITTAL
PRELIMINARY, NOT
FOR CONSTRUCTION

Detailed Engineer's Estimate						
Agency:		Tulare County Resource Management Agency				
Project Name:		Complete Streets- Lindsay				
Project Location:		E. Sierra View St - Standford Ave to I Ave/Rd 224 & Lafayette Ave - E. Tulare Rd to E. Sierra View St				
Date of Estimate:		August 26, 2021				
Prepared by:		Julian Sanchez				
Construction Items						
Item No.	Caltrans Item code	Description	Units	Quantity	Unit Cost	Total
1	999990	Mobilization	LS	1	\$198,000	\$198,000
2	050126	Construction Staking	LS	1	\$50,000	\$50,000
3	120090	Construction Area Signs	LS	1	\$15,000	\$15,000
4	120100	Traffic control system	LS	1	\$25,000	\$25,000
5	130200	Prepare Water Pollution Control Program	LS	1	\$10,000	\$10,000
6	70030	Lead Compliance Plan	LS	1	\$5,000	\$5,000
7	170103	Clearing and Grubbing	LS	1	\$25,000	\$25,000
8	220101	Finishing Roadway	LS	1	\$20,000	\$20,000
9(F)	190101	Roadway excavation	CY	4037	\$100	\$403,732
10(F)	250201	Class 2 Aggregate Base	CY	1919	\$100	\$191,852
11	390133	Hot Mix Asphalt (Type A)	TON	2451	\$120	\$294,144
12	731504	Minor Concrete (Curb & Gutter)	LF	6335	\$40	\$253,400
13	731521	Minor Concrete (Sidewalk)	SQFT	37700	\$8	\$301,600
14	731623	Minor Concrete (Ramp)	EA	21	\$5,000	\$105,000
15	731516	Minor Concrete (Driveway/V-gutter)	SF	8550	\$15	\$128,250
16	510502	Minor Concrete (Drainage Inlet)	EA	11	\$5,000	\$55,000
17	391006	Paving Asphalt (Binder to Geosynthetic)	TON	3	\$5	\$17
18	393004	Geosynthetic Pavement Interlayer (Fabric)	SQYD	3333	\$5	\$16,667
19	398200	Cold Plane Asphalt Concrete Pavement	SQYD	2633	\$10	\$26,333
20		Signing & Striping	LS	1	\$15,000	\$15,000
21		Misc Items	LS	1	\$35,000	\$35,000
22						
23						
					Sub-Total:	\$2,173,995
					*Contingency:	\$217,400
					TOTAL:	\$2,391,395
(F) = Final Pay Item						
* Up to 10% Contingency may be included in Engineer's Estimate						
Non-Construction Related Cost						
Item No.	Caltrans Item code	Description	Units	Quantity	Unit Cost	Total
22	-	Environmental Clearance	% of CON	5%	\$2,173,995.46	\$108,699.77
23	-	Preliminary Engineering (PE)	% of CON	10%	\$2,173,995.46	\$217,399.55
24	-	Construction Engineering (CE)	% of CON	15%	\$2,173,995.46	\$326,099.32
25	-	R/W Acquisition /Admin	LS	1	\$125,000.00	\$125,000.00
26	-	Utility Relocations	LS	0	\$100,000.00	\$0.00
					Total:	\$777,198.64
Total Construction & Non-Construction Items						\$3,168,593.64



RESOURCE MANAGEMENT AGENCY COUNTY OF TULARE AGENDA ITEM

BOARD OF SUPERVISORS

LARRY MICARI
District One

PETE VANDER POEL
District Two

AMY SHUKLIAN
District Three

EDDIE VALERO
District Four

DENNIS TOWNSEND
District Five

AGENDA DATE: December 14, 2021

Public Hearing Required	Yes <input type="checkbox"/>	N/A <input checked="" type="checkbox"/>
Scheduled Public Hearing w/Clerk	Yes <input type="checkbox"/>	N/A <input checked="" type="checkbox"/>
Published Notice Required	Yes <input type="checkbox"/>	N/A <input checked="" type="checkbox"/>
Advertised Published Notice	Yes <input type="checkbox"/>	N/A <input checked="" type="checkbox"/>
Meet & Confer Required	Yes <input type="checkbox"/>	N/A <input checked="" type="checkbox"/>
Electronic file(s) has been sent	Yes <input checked="" type="checkbox"/>	N/A <input type="checkbox"/>
Budget Transfer (Aud 308) attached	Yes <input type="checkbox"/>	N/A <input checked="" type="checkbox"/>
Personnel Resolution attached	Yes <input type="checkbox"/>	N/A <input checked="" type="checkbox"/>
Agreements are attached and signature line for Chairman is marked with tab(s)/flag(s)	Yes <input type="checkbox"/>	N/A <input checked="" type="checkbox"/>

CONTACT PERSON: Celeste Perez PHONE: 559-624-7010

SUBJECT: Adoption and Transmittal of Complete Streets Policy Plans for Plainview, Page-Moore, East Porterville and London

REQUEST(S):

That the Board of Supervisors:

1. Adopt the Complete Streets Policy Plans for Plainview, Page-Moore, East Porterville, and London.
2. Authorize Transmittal of these Complete Streets Policy Plans to the Tulare County Association of Governments.

SUMMARY:

Beginning in the fall of 2013, through funding from the Tulare County Association of Governments (TCAG) and intensive community outreach, Resource Management Agency (RMA) staff has worked diligently to finish 19 Complete Streets Programs, with 76 roadways planned, 24 roadways designed to 30%, and 36 selected for further Active Transportation Program (ATP) consideration, with 15 awards for direct ATP funding. These projects were completed by RMA Planning and Public Work's staff.

In 2019/20, TCAG awarded Tulare County \$140,708 for Plainview, Page-Moore, East Porterville, and London's Complete Streets Plans, through the Caltrans Sustainable Transportation Planning Grant Program. The grant award's deadline is January of 2022.

3. BOS Agenda 12.14.2021
 1. Agenda Item
 2. Resolution

SUBJECT: Adoption and Transmittal of Complete Streets Policy Plans for Plainview, Page-Moore, East Porterville and London
DATE: December 14, 2021

Complete Streets Policy Plan

The proposed Complete Streets Programs consists primarily of three parts: (1) Community Outreach and Selection, (2) Primary Project Selection with a 30% Design, and (3) Complete Streets Policy Plans.

Report Outcomes

The Complete Streets Plans achieve the following outcomes:

- Improve safety
- Address congestion and climate change
- Encourage walking and bicycling for health

These outcomes are intended to be achieved by addressing the following matters:

- Conducted extensive public outreach (20 Meetings) to ascertain the solutions that best fit within the context of these communities
- Created a comprehensive integrated and connected network of roadways that supports a multi-modal transportation approach
- Implemented the 2019 Updated General Plan Circulation Element Goals / Vehicle Miles Traveled Guidelines
- Planned for new and retrofit projects, including design, planning, maintenance, and operation
- Designed standards emphasizing flexibility - no one standard was applied to all streets

FISCAL IMPACT/FINANCING:

There will be no Net County Cost as the funding for this matter was grant funding provided by TCAG through Caltrans Transformative Climate Change program.

LINKAGE TO THE COUNTY OF TULARE STRATEGIC BUSINESS PLAN:

The County's five-year strategic plan includes the (i) "Economic Well Being Initiative - to promote economic development opportunities, effective growth management and a quality standard of living"; and (ii) "Quality of Life Initiative – to promote public health and welfare, educational opportunities, natural resource management and continued improvement of environmental quality."

SUBJECT: Adoption and Transmittal of Complete Streets Policy Plans for Plainview,
Page-Moore, East Porterville and London

DATE: December 14, 2021

ADMINISTRATIVE SIGN-OFF:

Aaron R. Bock, MCRP, JD, LEED AP
Assistant Director, Economic Development and Planning Branch

Michael Washam
Associate Director

Reed Schenke, P.E.
Director

Cc: County Administrative Office

Attachment(s) A – Complete Streets Plans for Plainview, Page-Moore, East
Porterville and London

BEFORE THE BOARD OF SUPERVISORS COUNTY OF TULARE, STATE OF CALIFORNIA

IN THE MATTER OF ADOPTION AND) Resolution No. _____
TRANSMITTAL OF COMPLETE STREETS)
POLICY PLANS FOR PLAINVIEW, PAGE-)
MOORE, EAST PORTERVILLE AND)
LONDON)

UPON MOTION OF SUPERVISOR _____, SECONDED BY
SUPERVISOR _____, THE FOLLOWING WAS ADOPTED BY THE
BOARD OF SUPERVISORS, AT AN OFFICIAL MEETING HELD DECEMBER 14,
2021, BY THE FOLLOWING VOTE:

AYES:
NOES:
ABSTAIN:
ABSENT:

ATTEST: JASON T. BRITT
COUNTY ADMINISTRATIVE OFFICER/
CLERK, BOARD OF SUPERVISORS

BY: _____
Deputy Clerk

* * * * *

1. Adopted the Complete Streets Policy Plans for Plainview, Page-Moore, East Porterville, and London.
2. Authorized Transmittal of all the Complete Streets Policy Plans to the Tulare County Association of Governments.

BEFORE THE BOARD OF SUPERVISORS COUNTY OF TULARE, STATE OF CALIFORNIA

IN THE MATTER OF Adoption and
Transmittal of Complete Streets Policy
Plans for Plainview, Page-Moore, East
Porterville and London

)
) Resolution No. 2021-1045
)
)


UPON MOTION OF SUPERVISOR VANDER POEL, SECONDED BY
SUPERVISOR VALERO, THE FOLLOWING WAS ADOPTED BY THE BOARD OF
SUPERVISORS, AT AN OFFICIAL MEETING HELD DECEMBER 14, 2021, BY THE
FOLLOWING VOTE:

AYES: SUPERVISORS MICARI, VANDER POEL, SHUKLIAN, VALERO AND
TOWNSEND

NOES: NONE


ABSTAIN: NONE

ABSENT: NONE



ATTEST: JASON T. BRITT
COUNTY ADMINISTRATIVE OFFICER/
CLERK, BOARD OF SUPERVISORS

BY:


Deputy Clerk

* * * * *

1. Adopted the Complete Streets Policy Plans for Plainview, Page-Moore, East Porterville, and London.
2. Authorized Transmittal of these Complete Streets Policy Plans to the Tulare County Association of Governments.